Coos County ST. 1853	Coos County Planning Department Land Use Application	FEE: Receipt No. 20993 Check No./Cash IIICS Date 5-28-19 Received By File No. 1015-19-072
Diates place a choi	le mark on the annropriate type of review t	that has been requested

Please place a check mark on the appropriate type of review that has been requested.

- Administrative Review
- □ Hearings Body Review
- ☐ Final Development Plan (BDR) ☐ Variance

An **incomplete** application **will not** be processed. Applicant is responsible for completing the form and addressing all criteria. Attach additional sheets to answer questions if needed. Please indicated not applicable on any portion of the application that does not apply to your request.

Α. **Applicant:**

Name: DAVE REED	Telephone: <u>541-551-0057</u>			
Address: P.O. Box 1608				
City: BANDON	State: Zip Code: 77411			

В. **Owner:**

Name:	RON LAFRANCHI	Telephone: <u>57/-396-537/</u>
Address:	5BO CENTROL BLUD	
City:	Coquilie	State: Zip Code: 9742.3

C. As applicant, I am (check one): Please provide documentation.

- The owner of the property (shown on deed of record);
- The purchaser of the property under a duly executed written contract who has the \square written consent of the vendor to make such application (consent form attached).
- A lessee in possession of the property who has written consent of the owner to make such application (consent form attached).
- The agent of any of the foregoing who states on the application that he/she is the duly authorized agent and who submits evidence of being duly authorized in writing by his principal (consent form attached).

D.	Description of Property:
Township	29s Range $12W$ Section 22 Tax Lot 101
Tax Account	1138700 Lot Size 6.15 Acre Zoning District <u>KR-5</u>
Updated 2016	

Information (please check off as you complete)

1. Project Proposal. Attach description if needed. Apontos TD EXISTING ActivENCE

- \varkappa 2. A detailed parcel map of the subject property illustrating the size and location of existing and proposed uses, structures and roads on an $8\frac{1}{2}$ " x 11" paper to scale. Applicable distances must be noted on the parcel map along with slopes. (See example plot map)Covenants or deed restrictions on the property, if unknown contact title company.
- 3. Existing Use Research
- 4. Site Address 95667 GUERIN MTRTLE
- 2 5. Access Road 42 m Guern
- 6. Is the Property on Farm/Forest Tax Deferral
- Current Land Use (timber, tarming, residential etc.)
- 8. Major Topography Features (streams, ditches, slopes) etc.) / Anti-5
- $\sqrt{2}$ 9. List all lots or parcels that the current owner owns, co-owns or is purchasing which have a common boundary with the subject property on an assessment

 \sim map. 22sl 2422 $\rho_{a} \in 10$ 102 10. Identify any homes or development that exists on properties identified in #9. None

□ 11.A copy of the current deed of record.

Proposed use and Justification F.

Please attach an explanation of the requested proposed use and findings (or reasons) regarding how your application and proposed use comply with the following the Coos County Zoning and Land Development Ordinance (LDO). Pursuant to the LDO, this application may be approved only if it is found to comply with the applicable criteria for the proposed use. Staff will provide you with the criteria; however, staff cannot provide you with any legal information concerning the adequacy of the submitted findings, there is no guarantee of approval and the burden rests on the applicant. (You may request examples of a finding)

List of Applicable Criteria and Justification:

THE ADDITION IS ENLARGING AN EX.	ISTING RESIDENTIAL STAVETURE
Whith is permitter overlight in The	E RR-5 ZONE THE ADDIELON
MAINTOINS THE AFOUNED SETARCA	5, BOTH BUILDING & FINE BACK

Updated 2016

E.

G. Authorization:

All areas must be initialed by all applicant(s) prior to the Planning Department accepting any application unless the statement is not applicable. If one of the statements, below is not applicable to your request indicated by writing N/A.

I hereby attest that I am authorized to make the application for a conditional use and the statements within this application are true and correct to the best of my knowledge and belief. I affirm that this is a legally created tract, lot or parcel of land. I understand that I have the right to an attorney for verification as to the creation of the subject property. I understand that any action authorized by Coos County may be revoked if it is determined that the action was issued based upon false statements or misrepresentation.

ORS 215.416 Permit application; fees; consolidated procedures; hearings; notice; approval criteria; decision without hearing. (1) When required or authorized by the ordinances, rules and regulations of a county, an owner of land may apply in writing to such persons as the governing body designates, for a permit, in the manner prescribed by the governing body. The governing body shall establish fees charged for processing permits at an amount no more than the actual or average cost of providing that service. The Coos County Board of Commissioners adopt a schedule of fees which reflect the average review cost of processing and set-forth that the Planning Department shall charge the actual cost of processing an application. Therefore, upon completion of review of your submitted application/permit a cost evaluation will be done and any balance owed will be billed to the applicant(s) and is due at that time. By signing this form you acknowledge that you are responsible to pay any debt caused by the processing of this application. Furthermore, the Coos County Planning Department reserves the right to determine the appropriate amount of time required to thoroughly complete any type of request and, by signing this page as the applicant and/or owner of the subject property, you agree to pay the amount owed as a result of this review. If the amount is not paid within 30 days of the invoice, or other arrangements have not been made, the Planning Department may choose to revoke this permit or send this debt to a collection agency at your expense.

I understand it is the function of the planning office to impartially review my application and to address all issues affecting it regardless of whether the issues promote or hinder the approval of my application. In the event a public hearing is required to consider my application. I agree I bear the burden of proof. I understand that approval is not guaranteed and the applicant(s) bear the burden of proof to demonstrate compliance with the applicable review criteria.

As applicant(s) I/we acknowledge that is in my/our desire to submit this application and staff has not encouraged or discouraged the submittal of this application.

Applicant(s) Original Signature

Applicant(s) Original Signature

Print Name

Updated 2016

2	Coos County Planning Department Coos County Courthouse Annex, Coquille, Oregon 97423 Mailing Address: Planning Department, Coos County Courthouse, Coquille, Oregon 97423
Coc	(541) 396-7770 FAX (541) 396-1022 / TDD (800) 735-2900
(e	Jill Rolfe Planning Director
	CONSENT
	On this day of 20_19,
	I, <u>Row LAFRANCH</u> (Print Owners Name as on Deed)
	as owner/owners of the property described as Township 295 , Range 124 ,
	Section, Tax Lot, Deed Reference
	hereby grant permission to
	(Print Application Type)
	County Planning Department.
	Owners Signature/s



GEOTECHNICAL STUDY AND REPORT RON LAFRANCHI

95667 GUERIN LANE MYRTLE POINT, OREGON

Pinnacle Engineering, Inc.

Matt Keller, PE, CSI Project Engineer President



Project #30122.03 23 May 2019

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page i of iv
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

INDEX

					Page
	Cover Index	•			i II, III, IV
Α.	EXEC	UTIVE SUMMARY			1
В.	INTRO B.1. B.2. B.3.	DUCTION Purpose and Scope Site and Project Descr Previous Geotechnica	iption I Report		1 1 2 2
C.	торо	GRAPHIC MAPPING			2
D.	GEOL D.1. D.2. D.3.	OGIC SITE CHARACTE Regional Geology Project Area Geology. Seismicity and Seismo D.3.a. Area and Site S D.3.b. Site Stability D.3.c. Site Classificat D.3.d. Seismic Refrac	RIZATION otectonic Considera seismicity ion tion Survey	ations	2 2 2 3 3 3 3 3 3 3 3 3 3 3 3 3
E.	FIELD E.1. E.2. E.3. E.4. E.5. E.6. E.7.	STUDIES Surface Reconnaissar Surface Hydrology Field Observations Site Exploration and F Geotechnical Characte Groundwater Soil Permeability	ice ield Testing erization		4 4 4 4 4 4 5 5 5 5
F.	LABO F.1. F.2. F.3. F.4.	RATORY TESTING Soil Classification Electro-Chemical Para Strength Parameters Performance Parameter	imeters		
G.	ENGII G.1. G.2.	NEERING STUDIES AND General Site Preparations and G.2.a. Clearing, Grubl G.2.b. Removal of Une G.2.c Density Testing	O RECOMMENDATIO Grading bing and Stripping. suitable Soil and Subgrade Rec	ONS	
	G.3.	Structural Fill Placeme G.3.a. Structural Fill M G.3.a.1 – SILT F G.3.b. Structural Fill F G.3.c. Compaction G.3.c1. Fill C G.3.d. Non-Structural	ent and Compaction Materials Fill soil Placement Observation and Tes Fill	n sting Methods	8 8 9 9 9 9 9 9
	G.4.	Slopes G.4.a. Cut Slopes G.4.b. Fill Slopes G.4.c. Slope Creep G.4.d. Recommended	Clearances		10 10 10 10 10 11
	G.5.	Paved Areas and Non-	Structural Slabs or	n Grade	
Pinna Email: I	cle Engi matt@pin	neering, Inc. nacleengineeringinc.com	3329 NE Stephens St. Roseburg, OR 97470	Phone (541) 440-4871 Fax (541) 672-0677	Page ii of iv Project # 30122.03

	G.5.a.	Asphaltic	Concrete Pavements	.11
	G.5.b.	Non-Stru	ctural Slabs on Grade	.11
G.6.	Site D	rainage ar	nd Erosion Control	.12
	G.6.a.	Buildings	5	.12
	G.6.b.	Crawlspa	ice Drainage	.12
	G.6.c.	Upslope	of Structures	.12
	G.6.d.	Surface A	Areas	.12
	G.6.e.	Erosion (Control	.12
G.7.	Buildi	ng Founda	ations	.13
	G.7.a.	General.		.13
	G.7.b.	Spread F	ootings	.13
		G.7.b.1.	Fill	.13
		G.7.b.2.	Footing Embedment	.13
		G.7.b.3.	Allowable Bearing Pressure	.13
			G.7.b.3.a Load Duration and Shape Increases	.13
		G.7.b.4.	Minimum Dimensions	.13
	G.7.c.	Footing D	Drains	.13
	G.7.d.	Settleme	nt	.13
	G.7.e.	Interior F	loor Slabs	. 14
		G.7.e.1.	Aggregate Base Course	.14
		G.7.e.2.	Underslab Membrane	.14
		G.7.e.3.	Minimum Slab Thickness	.14
		G.7.e.4.	Isolation	.14
		G.7.e.5.	Reinforcement	.14
		G.7.e.6.	Reinforcement Location	. 14
		G.7.e.7.	Fiber	.14
		G.7.e.8.	Joints	.14
	G.7.f.	Footing a	nd Floor Drains	. 14
		G.7.f.1.	Footing Drains	. 14
		G.7.f.2.	Wall Drains	. 15
		G.7.f.3.	Floor Subdrains	. 15
		G.7.f.4.	Discharge	. 15
G.8.	Latera	I Earth Pro	essures and Drainage	. 15
	G.8.a.	Lateral Lo	oad Resistance	. 15
	G.8.b.	Lateral E	arth Pressures	. 16
G.9.	Trencl	hing and F	Piping	. 17
		SERVICE	S AND LIMITATIONS OF REPORT	17
	Additi	onal Convi		17
п. I. Ц 2	Limita	tione	UC3	19
II.4 .	Liiiid			. 10

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page iii of iv
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

H.

FIGURES

Figure 1	Vicinity Map
Figure 2	Site Map
Figure 3	Geologic Reference
Figure 4	Geologic Map

APPENDICES

Appendix A	Tes	t Pit	Logs and	d Tests
------------	-----	-------	----------	---------

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page iv of iv
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

GEOTECHNICAL STUDY AND REPORT 95667 GUERIN LANE MYRTLE POINT, OREGON

A. EXECUTIVE SUMMARY

It is our opinion, supported by field investigations, laboratory tests and geotechnical analysis, that the existing and proposed site work, soils and geological conditions at the project site are suitable for the proposed structure, provided the recommendations of our report are incorporated during design and construction.

Special attention will be required during site preparation, construction of the building foundations and drainage features and other associated improvements. Subsequent sections of this report provide geotechnical recommendations for design and construction of the planned project.

- Local deposits of unsuitable soils may be encountered and would require excavation and disposal.
- Construction Materials Engineering and Testing (CoMET) services of site cuts and fills, compaction testing and observation of construction of slopes and drainage features is recommended.
- CoMET of structural fill and MSE or other retaining walls is required.
- Review of site and foundation design by the geotechnical engineer is recommended prior to beginning construction.

The following sections of this report provide geotechnical recommendations for design and construction of the planned project.

B. INTRODUCTION

B.1. Purpose and Scope

The property owner plans to construct a small single story addition to a home on the property. Construction of the addition is to consist of typical wood frame construction. Guerin Lane is located on a moderately to steeply sloped, generally westerly descending parcel located near the southern boundary of the City of Myrtle Point. Pinnacle Engineering, Inc. (PEI) has been engaged to prepare this report for use in site design and construction, to develop recommendations for embankment (cut and fill slope) construction and to recommend design parameters for foundations for the proposed structures.

Field investigations were conducted on 10 May 2019, and included a geologic reconnaissance of the site and immediate surrounding area, observation, sampling and testing of the underlying soils encountered in one test boring.

Soil samples were retrieved during site exploration for laboratory testing and other studies necessary to develop recommendations for design and construction of the foundations for the proposed structures, to evaluate potential complications that may occur during construction, to assess probable long term performance of the structures and for use in monitoring soil compaction.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 1 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

B.2. Site and Project Description

The proposed site is located in Section 19, Township 27S, Range 5W, W.M., in Myrtle Point, Oregon. The site is bounded to the south by Guerin Lane and is otherwise surrounded by undeveloped property on other sides. The site is located within 1000 feet of the Coquille River.

The project will result in the addition to a small home.

B.3. Previous Geotechnical Report

PEI is not aware that a prior geotechnical study report has been prepared for the above referenced site. Accordingly, this report (PEI) should be regarded as a residential geotechnical study and recommendations, consistent with the complexity of the proposed site and residential structure.

C. TOPOGRAPHIC MAPPING

Development of topographic mapping was beyond the scope of this study. Site slope measurements were measured on site by other means, where required.

D. GEOLOGIC SITE CHARACTERIZATION

Geologic and geotechnical terms used in this report are defined in Figure 3. Surface geologic mapping of the site is presented as Figure 4.

D.1 Regional Geology

The project site is located approximately 60 miles east of the Cascadia Subduction Zone. The Cascadia Subduction Zone reflects subduction of the Juan de Fuca plate beneath the western edge of the North American continental shelf.¹

D.2 Project Area Geology

The site is located within the Oregon Coast Range Geological province. Site soils consist of a thin layer of top soil overlying a thicker layer of silty clay. A layered matrix of residual turbidite sandstone and mudstone is intermixed and underlies the surface soils. The soil matrix overlies Early Eocene and late Paleocene Submarine Basalt flows at the project site.



Otter Point Formation (Jurassic) - A tectonically sheared assemblage of rocks including pervasively sheared sedimentary rocks (Jop) now prone to regional mass movement and subordinate amounts of sheared to intact volcanic rock (JOV), isolated blocks of thinly bedded tightly folded chert (Jc), exposures of serpentinite (Jsp), and isolated blocks of resistant blucschist (Js), a medium metamorphic rock. Soil types, thicknesses, and properties highly variable; major hazards include mass movement, slope erosion, stream bank erosion, and variable bearing strength.

Bulletin 87 – Environmental Geology of Western Coos and Douglas Counties, Oregon <u>Geologic Map of the Coquille Ouadrangle Oregon</u>, 1975, R.E. Corcoran, State Geologist, Oregon department of Geology and Mineral Industries.

1

Geology of the Pacific Northwest, 1999, Orr, Elizabeth L, and William N., Kendall/Hunt Publishing Company.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 2 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

D.3. Seismicity and Seismotectonic Considerations

Local faults generally trend from northeast to southwest, and include both normal and thrust type events. Inactive fault locations relative to the project site are depicted on Figure 4.

D.3.a. Area and Site Seismicity

Extensive seismotectonic studies continuing since 1990 have concluded that western Oregon is subject to a much greater likelihood of both random and platesubduction seismic events of far greater magnitude and far more frequently than was formerly believed.

- Regionally, the Cascadia Subduction Zone is considered as a feasible source of Magnitude 7.75, or greater, earthquakes.
- Intraplate earthquakes, focused at a relatively great depth within the Juan de Fuca plate subduction beneath western Oregon and Washington, are capable of producing magnitude 7.0 earthquakes. Deep focus intraplate earthquakes are theoretically possible, but considered rare in Oregon.
- Relatively shallow crustal earthquakes are more likely, with an upper bound considered to be on the order of Magnitude 5.75.

D.3.b. Site Stability

The soils underlying the project site are likely to be very stable during seismic events having a reasonable probability of occurrence. There is no likelihood of liquefaction, *tsunam* or *seiche*. Seismically induced landslides are possible but does not appear to be a concern.

D.3.c. Site Classification

The soil underlying the residential pad is consistent with Site Class C, as defined by the 2017 Oregon Residential Specialty Code (OSSC).

D.3.d. Seismic Refraction Survey

A seismic refraction survey was neither requested by our client nor conducted for this investigation. Qualitatively;

- Underlying the root zone, the low plasticity SILT material can be expected to transmit lateral accelerations typical of a lower velocity range of 800 to 1,200 ft/sec.
- Beneath the surface soils, the SILT grades to SANDSTONE, which can be expected to transmit lateral accelerations typical of a medium velocity range of 1,200 to 1,500 ft/sec.

Note, that areas of the site contain a thick layer of root zone and underlying organic soil that will require removal.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 3 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

E. FIELD STUDIES

E.1. Surface Reconnaissance

Contemporaneous with the geotechnical site characterization, a surface reconnaissance was conducted. The surface reconnaissance concluded that there were no observable site defects that would compromise viability of the site for the planned use.

E.2. Surface Hydrology

The subject site is located on a northerly trending margin of a moderately sloped hillside inclining north of Guerin Lane. The moderate slopes of the subject site can receive significant inflow from the slopes to the north and can facilitate a relatively rapid runoff of surface waters during rainfall events.

Cutting and filling activities will disturb the shallow perched water in a number of locations. This disturbance must be closely managed in order to avoid raising the phreatic surface within the embankment mass, possibly resulting in a decrease in stability.

Post development, the surface water runoff will be conveyed via gutters, ditches and storm drains then, ultimately, the Coquille River.

E.3. Field Observations

Field observations included soil description, classification, qualitative density measurement, measurements of thicknesses of the various soil horizons and depth to or presence of groundwater.

E.4. Site Exploration and Field Testing

Field investigations conducted on May 10, 2019 included geologic reconnaissance of the site and immediate surrounding area, and observation, sampling and testing in conformance to ASTM D-2488 of the underlying soils encountered in one test boring.

The test boring was advanced by use of a Little Beaver drill mounted on an all-terrain vehicle, which advanced 6 inch diameter continuous flight hollow stem auger at the location depicted on Figure 2. The test boring extended to a depth of 7 feet below ground surface. Soil samples were obtained using a split spoon sampler by method of Standard Penetration Test (SPT). Samples were sealed and stored for laboratory testing.

Samples were retrieved in the test boring at approximate 4 foot intervals and at visible soil horizon changes.. Bulk samples were retrieved at the depths and locations indicated on the test boring log.

In addition to basic field soil classification tests, *in situ* field density tests were conducted on natural site soils.

The test boring was left unfilled for a brief time to allow groundwater levels to stabilize if present. Groundwater was not encountered in the test boring.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 4 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

Please note that shear strengths and estimated bearing capacities noted on the field logs are field estimates of ultimate values, recorded for correlation of laboratory results and are only provided for comparative purposes. They should not be used for design. We should be contacted before utilization of values other than those recommended in Section G to confirm applicability and that the designer's interpretation is consistent with our understanding of design properties.

E.5. Geotechnical Characterization

Surface soils consist of high plasticity clayey SILT and extends to a depth of 3 feet below ground surface. Beneath the clayey SILT material, a layer of SILT containing traces of sand exists to a depth of approximately 7 feet below ground surface. Beneath the surface soils the SANDSTONE layer is estimated to be 10 feet below ground surface.

The shallow soils are compactible after removal of the vegetative component and may be used as non-structural or site fills if construction occurs during dry weather. The vegetative component is suitable for use as landscaping material or for sculpting wetlands mitigation areas.

The silt soils can be excavated with light to moderate effort by moderate energy excavation equipment. These materials should stand at relatively steep angles in shallow utility trenches. Deeper trenches will also stand at relatively steep angles initially, but seepage and wet weather combined with occasional weaker zones of soil increase the likelihood of sloughing.

Please note that soil descriptions and layer interfaces are interpreted from observations on site. While the layers are shown as having distinct boundaries in field logs, in reality, the change is gradual.

E.6. Groundwater

Groundwater (the phreatic surface) was not encountered during the field investigation. It is likely that the phreatic surface will fluctuate both seasonally and during the typical five year hydrologic cycle. Considering annual precipitation records during the past several years, the absence of measurable changes in the ground water surface should not be regarded as evidence that higher groundwater conditions will not occur in the future. Experience indicates that the phreatic surface will vary seasonally by approximately five feet and will vary by approximately ten feet between hydrologic extremes, an average ten year period. We project that the average high groundwater elevation will be approximately 8 feet below the finished surface. Seepage, occasionally in considerable amounts, should be expected at the transitional zone between the residual soils and the underlying transitional bedrock.

E.7. Soil Permeability

Although permeability tests were not performed for this study, experience indicates that flow velocities within the native shallow soils can be expected to range between 10^{-4} and 10^{-5} cm/sec and as high as 10^{-2} cm/sec at the bedrock interface where fine grained soils transition directly to weathered formational material. After compaction of the fills, permeability will likely decrease to range between 10^{-5} and 10^{-6} cm/sec. Where sandy layers exist, their permeability will be on the order of 10^{-3} cm/sec.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 5 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

F. LABORATORY TESTING

All of the samples recovered during the site exploration were visually reexamined at our Roseburg laboratory to verify the field descriptions. To assist in soil classification and assessing long term stability of the site soils, physical characteristics, including bearing capacity, consolidation, unconfined compressive strength, natural moisture/density relationship, plasticity indices and sieve analyses were determined for the fine grained portion of all samples. Samples were then classified in conformance with the Unified Soil Classification System (USCS) per ASTM D-2487.

F.1. Soil Classification

The USCS identifies soil type by single letter prefix and subgroup by single letter suffix as follows;

Table F 1 USCS Classification

Soil Type	Prefix	Subgroup	Suffix
Gravel	G	Well Graded	W
Sand	S	Poorly Graded	Р
Silt	Μ	Silty	Μ
Clay	С	Clayey	С
Organic	0	$w_L < 50$ per cent	L
Peat	Pt	$w_H > 50$ per cent	н

F.2. Electro-Chemical Parameters

Electro-Chemical analysis was neither requested nor conducted during this investigative effort.

F.3. Strength Parameters

For strength calculations, we recommend the following values for angles of internal friction and residual cohesion at 4% strain;

Table F 2 Strength Parameters					
Normal Load	Soil Type	Phi	Cohesion		
500 psf	Low plasticity clayey SILT	30 degrees	120 #/ft ²		
	Low plasticity sandy SILT	30 degrees	120 #/ft ²		
n i i i i i i i i i i i i i i i i i i i	Imported ABC FILL @ 90% density per D 1557	33 degrees	0#/ft ²		
3,000 psf	Low plasticity clayey SILT	34 degrees	360 #/ft ²		
	Low plasticity sandy SILT	34 degrees	240 #/ft ²		
	Imported ABC FILL @ 90% density per D 1557	37 degrees	200 #/ft ²		

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 6 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

Note that the above values are based on historic, typically minimum values determined in other tests of similar soils. For imported fill, we should be contacted to verify values after an actual fill source has been selected

F.4. Performance Parameters

In addition to the strength parameters described above, swell and consolidation characteristics of the natural soil were carefully considered, both in terms of primary and secondary (long term) volume change. Testing was conducted per ASTM D 2435 (modified), with saturation at a load of 225 psf to simulate the soil load resulting from a concrete slab and fill beneath the slab. The following volume changes were noted;

Table F 3 Performance Parameters					
Pressure	Consolidation (Swell)	Swell pressure	Location	Remarks	
225 psf	(0.4%)		TB 1 @ 4 feet	Low plasticity tan SILT	
1,500 psf	3.2%	-	TB 1 @4 feet	Low plasticity tan SILT	

Note that swell pressures listed in Table F 3 are recommended design values.

Recommended bearing pressures are presented in Section G of this report.

G. ENGINEERING STUDIES AND RECOMMENDATIONS

G.1. General

The engineering studies and recommendations summarized in this section provide design parameters for foundations for the proposed residential structure and for other appurtenant construction. Unless specifically noted otherwise herein, all density tests and recommended densities refer to the Modified Proctor (ASTM D 1557) at plus or minus 2% of optimum moisture.

For the purposes of this analysis, maximum column loads were assumed to be on the order of five kips. Wall loads were assumed to be on the order of one kip/lf. Construction methodology is assumed to consist of conventional light wood framing.

Pertinent geotechnical factors that may influence design and construction include;

- Control of both ground and surface water will be required during construction to facilitate constructability and during the life of the project to assure satisfactory long term performance.
- Stability of excavations during construction of all structures and trenches will require careful monitoring by the contractor.

G.2. Site Preparation and Grading

G.2.a. Clearing, Grubbing and Stripping

All areas proposed for roadways, structures, driveways, parking, walkways or structural fill should be cleared and grubbed of all trees, stumps, brush and other debris and/or deleterious materials. The site should then be stripped and cleared

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 7 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

of all vegetation, sod and organic topsoil. The depth for stripping is likely to vary between 6 to 8 inches. The removed material will consist of root zone.

PEI should be contacted to verify suitable subgrade.

G.2.b Removal of Unsuitable Soil

The top 24 inches of soil should be removed beneath the footings and replaced with a minimum of 12" of structural backfill.

Where areas of unsuitable soil, wood waste, building debris or other deleterious materials are encountered during excavation, they should be removed and replaced with compacted structural fill with the over-excavation lined with Type 2 drainage geotextile as recommended or specified by Engineer.

G.2.c. Density Testing and Subgrade Re-compaction

After stripping, the exposed subgrade should be tested per Oregon Department of Transportation Test Method 158 (ODOT TM 158) and observed by the geotechnical engineer's representative. Such testing should not be attempted in wet weather and should be discontinued if the subgrade pumps, deflects under load or otherwise deforms.

Where soils are disturbed or if they pump when tested, they should be excavated, moisture conditioned and re-compacted or be replaced with imported structural fill. Effective re-compaction of the fine grained soil will require moisture conditioning and will require less effort if compacted with a pneumatic or static sheepsfoot roller. Moisture conditioning and re-compaction beneath pavement or slabs should extend to a depth of between 10 and 12 inches. The re-compaction should achieve 90% of maximum density, as determined by ASTM D-1557

In locations where the subgrade consists of soils that are firm and generally unyielding, moisture conditioning and re-compaction is not required. We should be contacted to perform *in situ* strength tests of subgrade soils and to advise regarding moisture conditioning and compaction.

G.3. Structural Fill Placement and Compaction

Structural fill is defined as any fill placed and compacted to specified densities and located under roadways, structures, driveways, sidewalks and other load-bearing areas, and specifically includes all site fills more than 4 feet thick.

G.3.a. Structural Fill Materials

Structural fill should consist of a free-draining granular material with a maximum particle size of 8 inches or 2/3 of the un-compacted lift thickness, whichever is lesser. The material should be well graded with less than 5 percent non-plastic fines. During dry weather, any organic-free, non-expansive, compactable granular material meeting the maximum size criteria is typically acceptable for this use. Locally available crushed rock and jaw run crushed shale have performed adequately for most applications of structural fill.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 8 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

G.3.a.1. SILT Fill Soil - Where natural or imported SILT soil will be used to construct the building pad, driveway embankment or yard, they should be placed and compacted at 2% above optimum moisture and thoroughly worked in order to create a homogeneous fill. Some shrinkage cracks and long-term creep will likely occur on the surface of these SILT fill slopes during the life of the project.

G.3.b. Structural Fill Placement

Structural fill should be placed in horizontal lifts not exceeding 12 inches loose thickness, or thinner if necessary to obtain specified density. Each lift should be compacted to 90% of the maximum density. The lift thickness may be increased if specified density is consistently being exceeded and approved by the Engineer.

In order to accomplish effective compaction for the full fill footprint, we recommend that fills be over built by five feet, then the face cut back to achieve the design fill face.

Structural fill placed beneath footings or other structural elements should be centered on the footing. Thickness of the structural fill will vary depending on the depth of suitable bearing conditions. The width of structural fill should be equal to the width of footing plus twice the depth of the structural fill beneath the footing.

G.3.c. Compaction

To facilitate the earthwork and compaction process, the earthwork contractor should place and compact fill materials at 1% to 2% above their optimum moisture content. If fill source soils are too wet to compact, they may be dried by continuous windrowing and aeration to achieve optimum moisture. If soils become dry, moisture should be added to maintain the moisture content at or near optimum during compaction operations.

If soil having swell potential is used for fills beneath structures, it should be moisture conditioned at 2% to 4% over optimum and compacted to 88% of maximum density. Swell properties should be determined by laboratory testing prior to use as structural fill.

G.3.c.1. Fill Observation and Testing Methods - Field density testing by nuclear methods is appropriate for compaction of $2\frac{1}{2}$ - inch to $\frac{3}{4}$ - inch minus crushed base rock, fine grained soils, decomposed granite and other materials $2\frac{1}{2}$ inches or smaller in size. Due to the effect of particle size on test methods, other methods of compaction testing may be favored. Testing of only the upper lifts is not adequate to verify compaction.

G.3.d. Non-Structural Fill

All natural clayey SILT, waste soil, organic stripping or other deleterious soil is considered suitable only for non-structural fills. These materials may provide excellent landscape soils and lawn topsoil material if placed in landscape areas and waste soil areas, but should not be placed under permanent structures or within structural fill. It is recommended that these soils be compacted to 88%

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 9 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

relative compaction to help seal them from surface water. They should be utilized in berms less than 10 feet in height having slopes no steeper than 3 ½ H to1.0V.

G.4. Slopes

Temporary cut and low, permanent fill slopes will be required for construction of the site fill and structure building pads.

G.4.a. Cut Slopes

Permanent cut slopes will result from site excavation, overlot grading and placement of fills. Temporary cut slopes will be required for construction of retaining structures and other portions of the project. For brief periods, these may be excavated at steeper angles than listed above. The SILT soil may stand vertical to a depth of 4 feet for brief periods, except where saturated. In deeper trenches, side walls are likely to slough. We recommend cut slope angles no steeper than;

Table G 1 - Cut Slopes				
Soil Classification	Type of Cut	Inclination		
CLAY and SILT Soils	Temporary Cuts	1½ H to 1V		
CLAY and SILT Soils	Permanent Cuts	21/2 H to 1V		
Tan SILT w/ SHALE	Temporary Cuts	1 H to 1V		
Tan SILT w/ SHALE	Permanent Cuts	2 H to 1V		
Intact SHALE	Temporary Cuts	1/2 H to 1V		
Intact SHALE	Permanent Cuts	1 H to 1V		

G.4.b. Fill Slopes

If continuous CoMET services are provided, we recommend the following maximum permanent fill slope inclinations.

Table G 2 - Fill Slopes				
Soil Classification	Type of Fill	Inclination		
Fine grain soils (CLAY and SILT)	All	2 H to 1 V		
Tan SILT w/ SHALE	All	1¾ H to 1V		
Compacted, crushed base course	All	11/2 H to 1V		

All materials should be considered and constructed as Structural Fill, compacted as described above. In order to accomplish effective compaction for the full fill footprint, we recommend that fills deeper than six feet be over built by five feet width, then the face cut back to achieve the design fill face.

The underlying subgrade must be prepared and compacted prior to fill placement. Keys and benches are critical and must be excavated prior to placement of fill on sloping subgrade. Effective compaction is necessary. Use of sheepsfoot rollers is recommended to integrate each lift with the one below. Rubber-tired rollers can also achieve this result, but smooth-drum rollers should not be used. Care should be exercised when placing dried hard clay to avoid leaving voids within the fill mass, which voids may allow the soil to lose strength when wetted.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 10 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

G.4.c. Slope Creep

It is likely that surface creep will occur at locations where the organic SILT soils are utilized to construct fill slopes and in the organic layer of natural slopes. Creep will occur in response to seasonal volume changes resulting from variations in the moisture content. After repeated cycles a slight shift of the soil in the downslope direction will result and may become apparent.

G.4.d. Recommended Clearances

Recognizing the difficulty achieving specified density for unconfined soils, i.e., the edge of slopes, the minimum recommended separation between the crest or face of descending slopes and edge of footing should be 5 feet.

The minimum recommended separation between the ascending slopes and edge of footing should be 5 feet. Note that this is not a stability concern, but to provide access for future maintenance activities.

Note that, these slope setbacks apply to slopes constructed in conformance with this report. Slopes that have not been constructed in conformance with this report may require a greater set-back distance from toe or crest of slopes. Engineer should be contacted to verify suitable setback prior to placement of footings.

Note that, where minimum clearances recommended in this report from crests of slopes are not achievable, the footing bearing elevation may be deepened or it may bear on a deep foundation (drilled shafts or helical piers) to achieve the recommended clearance. Drilled shafts are favored over helical piers due to the greater bending strength. PEI can provide a required depth for deepened footings upon request.

G.5. Paved Areas and Non-Structural Slabs on Grade

G.5.a. Asphaltic Concrete Pavements

Site specific paving design was beyond the scope of this investigation, however, it should generally consist of compacted bituminous surface mix placed over a layer of 1 ½" minus aggregate base and compacted sub-base. Geotextile should be used as a separation medium to isolate localized sub grade failures For design purposes, CBR's can be expected to vary between 1 for soaked subgrade in fill areas to in excess of 20 in areas of competent weathered rock. If assistance is desired with site specific pavement design, please contact us.

Material quality and placement of the surface assembly should conform to the 2018 edition of the ODOT Standard Specifications for Highway Construction.

G.5.b. Non-Structural Slabs on Grade

Exterior concrete slabs on grade will be subjected to moisture induced movement which is likely to result in cracking and vertical offsets at joints and connections with other structures. More uniform support can be achieved by placing a minimum thickness of 8 inches of crushed rock, crushed shale or decomposed granite fill beneath the slabs in these areas and conforming to the concrete pavement recommendations per the Portland Cement Association. Slabs and

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 11 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

walkways reinforced with #3 or #4 deformed steel reinforcing bars both ways will also withstand moisture induced movement better than unreinforced flatwork. The reinforcing should extend across joints (or use dowels, Diamond Dowels, etc.) to decrease differential vertical movement. Jointing patterns to provide predetermined crack locations will also generally improve the appearance of the finished flatwork. Concrete work should conform to American Concrete Institute (ACI) Specification 306 and 318.

G.6. Site Drainage and Erosion Control

G.6.a. Buildings

Final grading should accomplish rapid positive drainage away from the structure for a horizontal distance of at least 10 feet at a minimum grade of 10%. This water should be channeled to surface drains or swales for proper disposal. The landscaping around the structure should be graded such that drainage discharges clear of the foundation influence area. Downspouts should be connected to a sealed system which discharges to a location clear of the foundation influence area.

G.6.b. Crawlspace Drainage

Crawl spaces should be sloped to drain to one or more low point drains. There should be no low areas that allow ponding. These low point drains should discharge through or under the foundations to the surface water disposal system.

G.6.c. Upslope of Structures

The area immediately upslope of most structures and components is likely to pond surface moisture. We recommend that the upslope area be graded to collect and dispose of surface moisture.

G.6.d. Surface Areas

Surface and subsurface water flows should be intercepted by swales and/or catch basins and conveyed through tight lines to acceptable discharge locations. We recommend that hard surfaces be provided, sloped and shaped to channel water away from the structure.

G.6.e. Erosion Control

Site soils are moderately susceptible to erosion if unprotected. The site grades are such that erosion and sediment transport during construction are not expected to be significant. The site cuts and fills, building pad, etc. should be graded such that surface water is collected and disposed without causing erosion or siltation. Sediment laden water should not be allowed to flow directly into streams or off-site drainage systems.

Typical project landscaping should be adequate for long-term erosion control.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 12 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

G.7. Building Foundations

G.7.a. General

A combination of spread and continuous footings is recommended for residential structures. To compensate for swell pressures, footings should bear on <u>non-swelling</u> imported structural fill.

G.7.b. Spread Footings

G.7.b.1. Fill – See Section G.2 and G.3 of this report.

G.7.b.2. Footing Embedment - Spread footings should be embedded a minimum of 12 inches below natural or finish grade to provide lateral support and frost protection. Footing excavations should be backfilled with structural fill.

G.7.b.3. Allowable Bearing Pressure – To calculate allowable bearing capacity, we assumed that the footing will be embedded 1 foot below the adjacent surface, yielding a D_f/B ratio of 0.75. Footings placed in this configuration may be designed for an allowable bearing pressure of 1,600 $\#/ft^2$.

G.7.b.3.a Load Duration and Shape Increases – Allowable bearing pressure may be increased by one-third for short term loads. Allowable bearing pressures on square spread footings may be increased by 20%.

G.7.b.4. Minimum Dimensions - The minimum recommended width for continuous footings is 1'- 4" and the minimum recommended dimension for spread footings is 1'-6".

G.7.c. Footing Drains

We recommend that exterior footing drains be provided for below grade components, located at an elevation low enough to intercept groundwater and limit it from rising above the surface of crawlspaces and the bearing area of interior slabs on grade. Footing drains should discharge clear of the foundation influence area. See Section G.7.f.

G.7.d. Settlement

Building settlement will vary with thickness and swell/consolidation potential of fill, type and thickness of underlying soils and methodology of foundation construction. In addition to settlement, vertical movement due to swelling of the foundation soil is possible for lightly or differentially loaded structural components placed on over-compacted non-natural imported soil having swell potential.

Relying on the loads estimated herein and assuming that the dead load portion will be approximately 1/3 of the total, we project total vertical movement to be up to 1 inch. Differential movement could be as much as 0.3 inches.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 13 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

G.7.e. Interior Floor Slabs

Interior floor slabs should not be rigidly connected to the perimeter footing, i.e., should float within the structure. The following recommendations are provided for slabs constructed on structural fill over properly prepared subgrade soils;

G.7.e.1. Aggregate Base Course (ABC) - A 6 inch thick layer of clean (less than 2% passing the No. 200 sieve) ³/₄" minus crushed rock should be placed over the structural fill to provide a positive capillary moisture break and uniform slab support. The capillary break is essential in areas to receive tile and linoleum and other areas with relatively impermeable floor finishes. To decrease drying stress, a ¹/₄ inch thickness of clean sand should be placed on top of the ABC.

G.7.e.2. Underslab Membrane - A moisture retarder or barrier should be used to decrease seepage or upward migration of moisture through the concrete, but is likely to increase soil moisture and exacerbate expansion if soils having expansion potential are imported. To protect the membrane, a 1/4 inch thickness of clean sand should be placed on top of the membrane.

G.7.e.3. Minimum Slab Thickness - Minimum recommended slab thickness is 5 inches to allow sufficient cover over the reinforcing steel. Note that all slabs should be designed for the actual use and equipment anticipated.

G.7.e.4. Isolation - Floor slabs and walls, both bearing and non-bearing, resting on floor slabs should be isolated from other structural components. We would be pleased to provide typical isolation details or to review structural plans prepared by others.

G.7.e.5. Reinforcement - The slabs should be reinforced with deformed reinforcing steel instead of welded wire fabric.

G.7.e.6. Reinforcement Location - Locate reinforcing a dimension of 1/3 slab thickness below the surface. Use "dobies" or bolsters to establish accurate position of reinforcement.

G.7.e.7. Fiber - Polypropylene fiber may be added to the concrete mix to help decrease plastic shrinkage cracking; however it is not a replacement for structural reinforcing.

G.7.e.8. Joints - Contraction and control joints conforming to ACI recommendations should be incorporated in the construction. Saw cut joints or wet scored joints should be accomplished within 12 hours after concrete placement. Construction joints and joints across dissimilar pours should be joined by square dowels to decrease the potential for differential vertical movement or curling.

G.7.f. Footing and Floor Drains

G.7.f.1. Footing Drains - Drains should consist of a rigid, smooth interior perforated drain pipe placed adjacent to the base of the footing. The

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 14 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

perforated pipe should be encapsulated in a minimum of 8 inches of clean drain rock or pea gravel wrapped in ODOT drainage geotextile Type 1.

G.7.f.2. Wall Drains - Drains are recommended for below grade walls. These walls should be provided a minimum 12-inch wide zone of drain rock isolated with non-woven drainage geotextile, continuous from the top of footing to one foot below the surface. A preformed, fabric-wrapped, polymer sheet drain, such as Linq Drain, Enkamat, or Amerdrain may be used instead of the vertical drainage zone, provided the excavation is backfilled with clean, free-draining material. Design of such walls should disregard friction between the wall and fill for stability computations, however. Walls demising habitable areas should be provided durable wall sealant coating or other water proofing membrane before installing the sheet drain.

G.7.f.3. Floor Subdrains - Where the drain rock layer below slabs will be lower than the adjacent exterior grades, water will tend to accumulate. In these locations, positive drainage of the under slab layer should be provided.

G.7.f.4. Discharge - Foundation drains and subdrains should be routed to discharge clear of the foundation influence area or slopes. *Interconnection of roof downspouts or surface area drains with foundation, wall, or floor subdrain systems is not allowed.*

G.8. Lateral Earth Pressures and Drainage

G.8.a. Lateral Load Resistance

Lateral loads exerted upon these structures can be resisted by passive pressure acting on buried portions of the foundation and other buried structures and by friction between the bottom of concrete elements of the foundations and slabs and the underlying soil.

Lateral load resistance should be calculated using the values presented in Section F.3 for the recommended depth of embedment as;

 $P_a \text{ or } P_p = \frac{1}{2} k_{(a \text{ or } p)} \gamma H^2 \text{ where;}$

P_a is active earth pressure

P_p is passive earth pressure

 $k_a = tan^2 (45^\circ - \phi/2)$

 $k_p = 1/k_a$

 γ = soil unit weight

The first one foot below the ground surface should be ignored when computing passive resistance.

- A coefficient of friction of 0.45 is recommended for elements poured neat against structural rock fill or bedrock.
- A coefficient of friction of 0.30 is recommended for elements poured against natural soils.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 15 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

• The above values should be reduced to 0.2 for areas where bearing is over a non-soil vapor barrier or low permeability membrane.

G.8.b. Lateral Earth Pressures

It is possible that both unrestrained and restrained retaining walls may be constructed for the project. Lateral earth pressures will be imposed on belowground and backfilled structures or walls, including daylight basements and foundations which do not have uniform heights of fill on both sides. The following recommendations are provided for design and construction of retaining walls:

- Walls which are free to rotate at the top when backfilled should be designed for an equivalent fluid pressure of 45 #/ft³. This value should be increased to 52 #/ft³ for a 2 H to 1 V back slope.
- Walls that are fixed at the top should be designed for an equivalent fluid pressure of 60 #/ft³. This should be increased to 67 #/ft³ for a 2 H to 1 V back slope.
- A wet soil unit weight of 135 #/ft³ should be used for design.
- Backfill should consist of non-expansive, free draining, soil material. The backfill should be placed in lifts at near the optimum moisture content and compacted to between 88 and 90 % of the maximum density. Care should be employed to avoid over compacting the backfill. Loosely placed backfill and over-compacted backfill will exert greater pressures on the wall than the pressures considered above.
- To prevent damage, backfill and compaction against walls or embedded structures should be accomplished with hand-operated equipment within a lateral distance of 1/2 to 1/3 the unsupported height of wall. Beyond this zone, normal compaction equipment may be used.
- While proper compaction of wall backfill is critical to long-term performance, care should be taken to avoid over compaction of the backfill materials, which can result in lateral loads greater than the design pressures recommended above.
- For design of retaining walls supporting or bracing structures, a peak horizontal acceleration coefficient of 0.2g is recommended for seismic loads.
- To prevent development of hydrostatic pressures exceeding the lateral earth pressures, a perimeter drainage system is recommended for underground structures, including basements.
- Hydrostatic pressures behind retaining walls should be relieved by installation of free draining backfill behind the walls, with weep holes spaced as necessary (typically 10 feet on center) to achieve effective drainage. The free draining backfill should be protected from plugging by encapsulating with drainage geotextile as recommended above.
- Allowable bearing capacities should be as recommended for Building Structures.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 16 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

G.9. Trenching and Piping

Additional underground piping will be constructed. Excavation can be accomplished by normal means above the rock elevations projected to underlie the site at an average depth of 2 to 6 feet. Depending on when construction occurs, dewatering of the trench may be necessary to facilitate construction.

- Pipe should be cradled in coarse aggregate compacted to 90% density, having a minimum thickness equal to 1/4 pipe diameter below bottom of pipe and extending upward to the pipe spring line.
- The trench backfill should consist of clean excavated material, compacted to 90% density.
- Beneath paved areas, full depth granular backfill is recommended as a minimum, and use of lean cement slurry should be considered.
- The top 12" of trench backfill should be compacted to a density of 92%. Loads on pipe will vary with depth and width of trench.
- For pipe design, an effective pressure of 130 #/ft³ per foot of depth is recommended.

Underground pipes located beneath paved areas and having shallow cover should be designed to withstand vehicular loads.

H. ADDITIONAL SERVICES AND LIMITATIONS OF REPORT

H.1. Additional Services

Additional services by the geotechnical engineer are recommended to help insure that design recommendations are correctly interpreted during final project design and to help verify compliance with project specifications during construction. Additional services could include, but not be limited to:

- Review of final construction plans and specifications for compliance with geotechnical recommendations.
- Attend project team meetings to clarify issues raised during the construction process.
- Review and/or design of swale, fill and basement subdrain systems.
- Review of proposed cuts and fills, fills on slopes, surface and subdrains, swale drains, foundation support, and basement or rock fill subdrains.
- Site observation and/or CoMET services, i.e., observation of over excavated areas below keys, benches and footings and slabs, subgrade proof rolling, placement and compaction testing of structural fill, fill subdrains, swale subdrains, foundation drains, wall drains, subgrade proof rolling, pavement subgrade and aggregate base placement, site grading, surface drainage, etc.
- Special Inspection as defined by the OSSC may be required for certain of the components.
- Periodic construction field reports, as requested by the client and required by the building department

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 17 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

H.2. Limitations

Where used herein, the terms "Special Inspector, Inspector and Special Inspection" are understood to be for services contemplated, prescribed and as defined by the International Building Code and the Oregon Structural Specialty Code.

The analyses, conclusions and recommendations contained in this report are based on site conditions and development plans as they existed at the time of the study, and assume that soils and groundwater conditions encountered, observed or inferred during our exploration are representative of soils and groundwater conditions throughout the site. If, during construction, subsurface conditions are found to be different or design parameters change, we should be advised at once so that we can review this report and reconsider our recommendations, as appropriate. If there is a significant lapse of time between submission of this report and the start of work at the site, if the project is changed, or if site conditions have changed, we recommend that this report be reviewed to verify continued applicability.

This report was prepared for the use of the owner and design team for the subject project. It is only for this site and construction project. No third party beneficiaries are intended. Potential users of the report should be so notified.

It should be made available to other contractors for information and factual data only, such as test boring or test pit logs, measured water levels, samples, sample classifications and laboratory test results. The report is interpretive in nature and shall not be used for contractual purposes, such as warranting that subsurface conditions will be consistent with, or as indicated by the formal boring or test pit logs and subsurface profiles contained or inferred herein and/or discussions of subsurface conditions. It is not to be used for extensions of this project or for other projects without our express written consent. We should be contacted to review both plans and specifications for compatibility with this report before finalization. **CoMET services, compaction testing and periodic observation during construction are recommended.**

We have performed these services in conformance with generally accepted engineering and geotechnical engineering practices in southern Oregon at the time the study was accomplished. No other warranty is either expressed or implied.

Since test pits and borings represent only the conditions at those discrete locations, unanticipated soil conditions may be and, in fact, are commonly encountered on projects of similar size. Unanticipated conditions cannot be precluded by practical field studies. Since such unexpected conditions frequently result in budget increases to attain a properly constructed project, we recommend that a reasonable contingency account be established sufficient to fund possible extra costs.

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 18 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

FIGURES

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page 19 of 19
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03







SUBSURFACE SOILS INVESTIGATION SITE MAP PROJECT: 30122.03 - 95667 GUERIN LANE - GEOTECH

PROJECT: 30122.03 - 95667 GUERIN LANE - GEOTECH CLIENT: RON LAFRANCHI FIG. 2

SOIL TYPES (Ref. 1)

Boulders:	Particles of rock that will not pass a 12 inch screen.
Cobbles:	Particles of rock that will pass a 12 inch screen, but not a 3 inch sieve.
Gravel:	Particles of rock that will pass a 3 inch sieve, but a #4 sieve.
Sand:	Particles of rock that will pass a #4 sieve, but not a #200 sieve.
Silt:	Soil that will pass a #200 sieve, that is non-plastic or very slightly plastic, and exhibits little pr no strength when dry
Clay:	Soil that will pass a #200 sieve, that can be made to exhibit plasticity within a range of water contents, and that
	exhibits considerable strength when dry

MOISTURE AND DENSITY

Moisture condition:	An observational term; moist, wet.
Moisture content:	The weight of water in a sample divided by the weight of dry soil in the sample, expressed as a
	percentage.
Dry Density:	The pounds of dry soil in a cubic foot of soil

DESCRIPTORS OF CONSISTENCY (Ref. 3)

Liquid Limit:	The water content at which a - #200 soil is on the boundary between exhibiting liquid and plastic
	characteristics. The consistency feels like soft butter.
Plastic Limits:	The water content at which a - #200 soil is on the boundary between exhibiting plastic and semi-solid
	characteristics. The consistency feels like stiff putty.
Plasticity Index:	The difference between the liquid limit and the plastic limit, i.e. the range in water contents over which the
	soil is in a plastic state.

MEASURES OF CONSISTENCY OF COHESIVE SOILS (CLAYS) (Refs 2&3)

Very soft	N=0-1*	C=0-250 psf	Squeezes between fingers
Soft	N=2-4	C=250-500 psf	Easily molded by finger pressure
Medium stiff	N=5-8	C=500-1000 psf	Molded by strong finger pressure
Stiff	N=9-15	C=1000-2000 psf	Dented by strong finger pressure
Very stiff	N=16-30	C=2000-4000 psf	Dented slightly by finger pressure
Hard	N>30	C>4000 psf	Dented slightly by pencil point

*N= Blows per foot in the Standard Penetration Test. In cohesive soils, with the 3 inch diameter sampler. 140-pound weight, divide the blow count by 1.2 to get N (Ref. 4).

MEASURES OF RELATIVE DENSITY OF GRANULAR SOILS (GRAVELS, SANDS, SILTS) (Refs 2 & 3)

Very Loose	N=0-4**	RD=0-30	Easily push a ¹ / ₂ inch reinforcing rod by hand
Loose	N=5-10	RD=30-50	Push a 1/2 inch reinforcing rod by hand
Medium Dense	N=11-30	RD=50-70	Easily drive a ¹ / ₂ inch reinforcing rod
Dense	N=31-50	RD=70-90	Drive a 1/2 inch reinforcing rod 1 foot
Very Dense	N>50	RD=90-100	Drive a 1/2 inch reinforcing rod a few inches

**N= Blows per foot in the Standard Penetration Test. In granular soils, with the 3 inch diameter sampler, 140 pound weight, divide the blow count by 2 to get N (Ref 4). RD = Relative Density.

Ref. 1: ASTM Designation: D 2487-93, Standard Classification of Soils for Engineering Purposes(Unified Soil Classification system). Ref.2: Terzaghi, Karl, and Peck, Ralph B., <u>Soil Mechanics in Engineering Practice</u>, John Wiley & Sons, New York, 2nd Ed., 967, pp. 30, 341, 347.

Ref.3: Sowers, George F., <u>Introductory Soil Mechanics and Foundations: Geotechnical Engineering</u>, Macmillan Publishing Company, New York, 4th Ed., 1979, pp. 80,81, and 312.

Ref.4: Lowe, John III, and Zaccheo, Phillip F., Subsurface Explorations and Sampling Chapter 1 in <u>Foundation Engineering Handbook</u>, Hsai-Yang Fang, Editor, Van Nostrand Reinhold Company, New, 2nd Ed, 1991, p.39/



SUBSURFACE SOILS INVESTIGATION GEOLOGIC REFERENCE

PROJECT: 30122.03 - 95667 GUERIN LANE - GEOTECH CLIENT: RON LAFRANCHI FIG. 3



LE PROJECT: 30122.03 - 95667 GUERIN LANE GEOTECH ENGINEERING, INC. **CLIENT: RON LAFRANCHI** 3329 NE STEPHENS ROSEBURG, ORGON 97470 PH:541-440-4871 FAX:541-672-0677 www.pinnacleengineering.com

FIG. 4

APPENDIX A TEST BORING LOG AND TESTS

Pinnacle Engineering, Inc.	3329 NE Stephens St.	Phone (541) 440-4871	Page A
Email: matt@pinnacleengineeringinc.com	Roseburg, OR 97470	Fax (541) 672-0677	Project # 30122.03

	TEST LOG	PROJECT: 95667 GUER	PROJECT: 95667 GUERIN LANE F CLIENT: PINNACLE ENGINEERING, INC. F								60321.2 10/19	.2
	TB1	24°6 V 9	00X	W MOUN	TED DRIL	L WITH 4	_ ELE _ LOG " AUG	ELEVATION: 114 LOGGED BY: TSK AUGER SEEDAGE:				
"ile: 603.	21 Date Printed: 5/16/2	019				T	Π.			TEST RE	SULTS	_
DEPTH (feet)	Descrip	Recov (in	Recov (in Driven (in	PID ppm	Sample#	Soil Type Samler	Symbol	Plastic Lir Water Col	nit ⊢ 20 30	i Li	quid Li	
0 -	ROOT Z	ONE					http://www.com/					
	MH-clayey SILT, dark brown to black	c, very moist to wet, medium stiff							-			
_										: :	:	<u>:</u>
2 -						25055						:
_						35055						+
	ML-SILT w/ some rounded gravel and	I traces of sand, dark gray, moist,				35056	вА	G	-			
	stiff								<u></u>		:	:
-	Qc=1	5	8	18		35057	SP			3-6-7 (N=13): :	:
	· · · · · ·										:	<u>:</u>
								-	<u> </u>			
6 -												
_			6	10		25059	CD	-		2.4.11	(NI-15)	
	FND TEST BORE	ng Qc=1 /		10		33030						
в -	DRILL REI clayey SAND at b	FUSAL ottom of hole									:	<u> </u>
								-				
_									<u> </u>			
0-												
-			. 820									<u> </u>
									-			
-												<u></u>
2-												1
-												<u>:</u> :
	and the second sec											
4-			с 721				1					
-												
-1									:	:	:	:

Figure

PAGE 1 of 1

Western Testing, LLC

Western Testing, LLC Construction Materials Jesting Quality Results, Always,	Roseburg C 3329 N.E. Si Roseburg, C Ph: (541) 95 Fax: (541) 6	office Rephens IR 97470 7-1233 72-0677	Coast Office Ph: (541) 26(- 5-9375	NATURAL MOISTURE DENSITY REPORT					
PROJECT: 95667 GUERIN LN. MYRTLE P	OINT			PROJEC	T NO: 60321	.2				
CONTRACTOR: PEI		-			I	DATE: 5/13/19				
SUEJECT: NATURAL MOISTURE AND DE	INSITY	-	1	Sun Mon	Tues Wed	Thurs Fri Sat				
Tested By: <u>TJB</u>			Testing	Date: 05/13/1	19					
BORE HOLE TE 1@ 4'										
LENGTH 1 (in.) 4.3										
LENGTH 2 (in.) 4.1		Į								
LENGTH 3 (in.) 4.2			.							
AVG LENGTH (in.) 4.20	<u> </u>									
DIAMETER 1 (in.) 1.9										
AVG DIAMETER / in V 1 00										
VOLUME (# ³) 0.01										
TARE (gram) 32.5		27201421		같은 관련을 관할	en e					
WET + TARE (gram) 401.7										
DRY + TARE (gram) 355.4		书标的过去								
DRY WEIGHT (gram) 322.9 0	0	0	0	0	0	0				
% MOISTURE 14.3%	0	0.	0	0	0	0				
DENSITY (PCF) 103.6		<u></u>	1							
BORE HOLE	1	r								
SAMPLE NO.										
LENGTH 1 (in.)										
LENGTH 2 (in.)										
AVG LENGTH (in)										
DIAMETER 1 (in.)	<u> </u>		<u> </u>							
DIAMETER 2 (in.)										
AVG DIAMETER (in.)		•								
VOLUME (ft ³)										
TARE (gram)						 Martin Martin M Martin Martin Ma Martin Martin Marti				
DDV + TADE (gram)						가게 특히는 수많은 것 				
DRY WEIGHT (gram) 0 0		0			an sanaan Gertaa					
WATER (gram) 0 0	0	o	0	0	0	0				
% MOISTURE					Ţ					
		r	r							
	<u>I</u>		I							
REMARKS:	· · · · · · · · · · · · · · · · · · ·					·····				
				·	·····					
	25									
Reviewed By:	-				Date:					

e

J,

* "Special Inspection", "Inspection" and "Inspector" are terms as defined by the International Building Code





Tested By: TJB

											0			6			
										eo	0.57	H H		1/51/5	FIED.		
										Swell %	0.4	AAS		TSK ON	135 MODI Itsf, pH=8		Figure
									2000	Swell Press. (psf)	260	uscs		kemarks: TEST RAN BY	PER ASTM D24 PP=1.5tsf, TV=4		
ORT										ণ্					<u></u>		
ЯПР И				-			~			ပိ			stiff				
TEST									1000 ssure - psf	P _c (psf)			k gray, moist,	, INC.	/Depth: 4		
ATION	Q								500 Applied Pre	Overburden (psf)	414	CRIPTION	aces of sand, dar	ENGINEERING	7 Elev	ig, LLC	egon
OLID			/							છું છુ	2.8	AL DES	/el and tra Qc=15	NACLE	o.: 3505'	Testir	urg, Oi
SNO NO	WATE									ā		AATERI	ided grav	nt: PIN	mple N	stern	cosebi
ö		4							8	E		4	me rour	NE Clier	Sa	We	Ľ.
									3	Dry Dens. (pcf)	111.3		-SILT w/ so	21.22 JUERIN LA			
									100	Moist.	10.2 %		MI	No. 603. 95667 G	TBI		
	.005	000.	.005	-ini - jrhpiəl- Ş	in 5 1 ul ebusu;	 .025	.030	.035	.040 -	Natu Sat.	50.3 %			Project I Project:	Source:		

LAFRANCHI ADDITION 95667 GUERIN LANE MYRTLE POINT OR. 97458



BANDON OREGON DAVID REED / 541-551-0057